

DISTRICT BOARD, TUMKUR.

Notification No. C. 670—34-35, dated 24th January 1935.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Tumkur, up to 2 P.M., on the 14th February 1935, for sinking a well for raiyats in Banasandra, Tiptur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the 30th May 1935.

2. The plan and the detailed estimate may be seen at the Office of the President, District Board, between the hours of 11 A.M. and 5 P.M. except on Sundays and authorised Public Holidays.

3. Tenders should be submitted on typed forms, which may be obtained from the Office of the President. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 25 (twenty-five) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for sinking a well for raiyats in Banasandra Village" in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the President, District Board, Tumkur, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the President's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates should be written legibly both in figures and words without correction.

10. The contractor will not be allowed to claim enhanced rates after the submission of the tender at any stage.

11. The decision of the President, District Board, will be final and legally binding on the contractor in case of disputes about the rates, qualities and quantities of work.

ABSTRACT OF THE ESTIMATE.

Sl. No.	Items of work	Quantity	Per	Rate
				Rs. a. p.
1	Earthwork excavation in ordinary reddish soil from			
	0' to 6'	39.3	C.yds.	
	Do in Sudde Soil 6' to 12'	39.3	"	
	Do do 12' to 18'	36.6	"	
	Do do 18' to 24'	36.6	"	
	Do do 24' to 30'	34.2	"	
	Do do 30' to 36'	34.2	"	
2	Burnt stone revetment with jelly backing	133	"	
3	Baling charges	Lumpsum	Lumpsum	
4	Burnt stone slabs 6" thick roughly dressed one line (lead about 11 miles)	335	S.ft.	
5	Burnt stone slabs 4" do	469	"	
6	Parapet wall in burnt stone in chunam mortar	173	C.ft.	
7	Providing strong wooden pulleys with iron bars, etc., .. complete	4	Each	
8	Cement pointing for platform of the well	4	Sqr.	
9	Burnt stone work dry for retaining wall	150	C.ft.	
10	Earthwork for platform	Lumpsum	Lumpsum	
11	Chunam pointing for steining	6.28	Sqr.	

H. VENKATARAMAIA,
President.

OFFICE OF THE SUPERINTENDENT, IRWIN CANAL FARM, MANDYA.

Notification, dated 25th January 1935.

1. Sealed tenders for installing Electric Lights to the Accountants' and Clerks' quarters on the Irwin Canal Farm, Mandya (8 miles from Mandya station) are received from the licensed electric contractors up to 3 P.M. on Saturday the 16th February 1935.

2. The tender should be properly sealed and superscribed "Tenders for installing electric lights to Accountants' and Clerks' quarters on Irwin Canal Farm" and should accompany with a deposit of Rs. 25 which will be returned to the unsuccessful tenders after the tender is finally accepted.

3. The approximate quantity of work of each building is mentioned in the schedule enclosed and cannot be guaranteed.

4. The work should be completed within 2 weeks from the date of acceptance of the tender, failing which a penalty of Re. 0-4-0 per day of delay will be levied.

5. The tenderers should deposit a sum of Rs. 50 for the due fulfilment of the contract which will be returned on completion of the work satisfactorily.

6. Tenders without specific rates for the items such as 2 per cent or etc., less than the estimated cost or of the lowest tender cannot be considered.

7. The completed work will be inspected and tested by the Electric Department whose approval will be final.

8. The damaged masonry should be repaired and the casing, etc., painted to suit the colour wash.

9. The materials to be used on the work should be of best quality either English or American and the tenders should specify clearly the make of the materials offered, the wire should be of 2,500 Megohm grade.

10. Any minor deviations that might be suggested in the course of the work should be carried out without any extra cost.

11. The final acceptance of the tender will rest with the Director of Agriculture in Mysore, Bangalore, who does not bind himself to accept the lowest tender or assign any reasons whatsoever for the rejection of any tender.

12. Within three days after the acceptance of the tender, the successful tenderer will be required to execute an agreement on a stamped paper, undertaking to fulfil the contract satisfactorily.

13. In the event of the accepted tenderer failing to comply with any of the conditions stipulated above, his contract shall be forthwith cancelled and the money deposited will be forfeited to Government and the work got executed by separate agency at the risk and expense of the tenderer.

Estimate for installing Electric Lights to the Accountants' and Clerks' quarters on the Irwin Canal Farm.

APPROXIMATE QUANTITY OF WORK OF EACH BLOCK.

Serial No.	List of materials required for each of the above buildings	Unit	Quantity
1	Supplying, fixing S. M. rail 24' long and tarring the same ..	No.	1
2	Supplying 2 pin D.C.A. complete with clamps bolts and nuts distance pipe pieces	"	1
3	Supplying Insulator with pins	"	4
4	Supplying guy set complete with rod anchor and guy wire 7 strand ..	Set	1
5	Supplying No. 8 B. & S. bare copper wire lead and return ..	lbs.	16
6	Supplying and running mains in $\frac{1}{2}$ " W. I. pipe with necessary bands 3 set of clamps using No. 14 B. & S. insulated wire ..	ft.	30
7	Supplying Earthing the main pipe	No.	1
8	Supplying, fixing and wiring varnished T. W. board 18"×15"×1" with battens 2" high and rear board $\frac{1}{2}$ " thick and equipping it with a 5 amp. D.P. linked switch two 5 H.P. bow cut out using 14 B. & S. insulated wire	"	1
9	Supplying, fixing and wiring in standard T. W. casing, treated with 2 coats of shelloack varnish for drop light with ceiling roses flexible cords, Lamp holders B.C.C.G. 5 Amp. Tumbler switch using No. 14 B. & S. Insulated wire	"	3
10	Supplying, fixing and wiring in standard T. W. casing with two coats of shelloack varnish for bracket brass 9"× $\frac{1}{2}$ " with B.C. lamp-holder 5 H.P. tumbler switch using No. 14 B. & S. insulated wire	"	4
11	Supplying and fixing shades—Longham	"	7
12	Supplying Lamps 220 V. B.C. 20 to 60 watts	"	7

C. E. RAMIAH,
Superintendent.